

WEST BENGAL MEDICAL SERVICES CORPORATION LTD.

(Wholly Owned by the Government of West Bengal)

CIN: U85110WB2008SGC126373

Regd. Off. : Swasthya Sathi, GN-29, Sector-V, Salt Lake, Kolkata-700091

Telephone: (033) 40340300 | Fax: (033) 40340400

E-mail: info@wbmsc.gov.in | Website: www.wbmsc.gov.in

Memo No.: WBMSC/AAES- 768/4230

Date: 24/11/2017

ORDER

Administrative Approval & Expenditure Sanction is hereby accorded for 'Civil work relating to Construction of new plant cum manifold room for Medical Gas Pipe Line System (MGPS) at Uluberia SDH, district Howrah' at an estimated cost of Rs. 22,34,977.00 (Rupees Twenty Two Lakh Thirty Four Thousand Nine Hundred and Seventy Seven) only against fund allotment No: 1517(Sanction)/HF/P/P&B/MS/W-55/2017 Dated 23/11/2017

The details are as follows:

Sl No	Schemes	Amount (Rs)
1	Civil work relating to Construction of new plant cum manifold room for Medical Gas Pipe Line System (MGPS) at Uluberia SDH, district Howrah	21,80,465.00
2	Contingency @ 2.5%	54,512.00
Total		22,34,977.00

The work will be executed by the Executive Engineer, P.W.D, Howrah Construction Division & Ex-Officio Executive Engineer, West Bengal Medical Services Corporation Limited, as per norms stated in the order of the Health & Family Welfare Dept. M.S. Branch, vide No. HF/O/MS/384/W-39-12 dt. 01.06.2012 read with Notification No. 86-W(C)-1M-106/11 dt. 06.02.2012 and Memorandum no 37-W(C)-1M-106/11 dated 17.01.2012 of Public Works Department, Government of West Bengal.


Managing Director

Memo No: WBMSC/AAES-768/4230/1(9)

Date: 24/11/2017

Copy forwarded for information and necessary action to:

1. Joint Secretary, M.S. Branch, Dept. of Health & Family Welfare
2. CMOH, Howrah
3. Superintendent, Uluberia SDH
4. Superintending Engineer, PWD, Nabanna Circle & Ex-Officio Superintending Engineer, West Bengal Medical Services Corporation Limited
5. Manager (Accounts), West Bengal Medical Services Corporation Limited.
6. Executive Engineer, P.W.D, Howrah Construction Division & Ex-Officio Executive Engineer, West Bengal Medical Services Corporation Limited
7. Consultant Project Engineer (Civil), West Bengal Medical Services Corporation Limited
8. Consultant Mechanical Engineer, West Bengal Medical Services Corporation Limited
9. Office Copy.


Managing Director



সংসদে স্বাক্ষর

GOVERNMENT OF WEST BENGAL
OFFICE OF THE EXECUTIVE ENGINEER, (P.W.D.)
HOWRAH CONSTRUCTION DIVISION
2, MAHATMA GANDHI ROAD, (1ST FLOOR), HOWRAH - 711 101

MEMO NO: - 760

DATE: - 06.07.17

TO,
THE MANAGING DIRECTOR & SECRETARY
HEALTH & FAMILY WELFARE DEPARTMENT
SWASTHYA SATHI, GN-29, SECTOR - V,
SALT LAKE, KOLKATA-700 091


Sub: - Construction of a new plant cum manifold room for medical gas pipe line system at Uluberia Sub Divisional Hospital, Uluberia, Howrah


Ref: vide memo no. WBMSC/PROC/1887/17/1872 dated 12.06.2017

Kindly refer to the memo quoted above the undersigned sends herewith above noted estimates amounting to **Rs. 2245879.00** only for on ward transmission to the competent authority duly countersigned by him on the body of the estimates no - **8 of 2017-18** for administrative approval and placement of fund to P.W.D. in favour of the undersigned. The minor error occurs in the calculation due to rounding of amounts. It is also to be mentioned that these estimates will valid for 2017-18.

As per discussion with The Executive Engineer, Electrical the estimate of Electrical portion will be send separately from his end.

**Enclosure: - Technically sanctioned copies of
Estimates No - 8
(in Duplicate)**


Executive Engineer, (P.W.D.)
Howrah Construction Division

o/e 
06/07/17



স্বাস্থ্য বিভাগ

GOVERNMENT OF WEST BENGAL
OFFICE OF THE EXECUTIVE ENGINEER, (P.W.D.)
HOWRAH CONSTRUCTION DIVISION
2, MAHATMA GANDHI ROAD, (1ST FLOOR), HOWRAH – 711 101

MEMO NO: - 760

DATE: - 06.07.17

TO,
THE MANAGING DIRECTOR & SECRETARY
HEALTH & FAMILY WELFARE DEPARTMENT
SWASTHYA SATHI, GN-29, SECTOR – V,
SALLAKE, KOLKATA-700 091


Sub: - Construction of a new plant cum manifold room for medical gas pipe line system at
Uluberia Sub Divisional Hospital, Uluberia, Howrah


Ref: vide memo no. WBMSC/PROC/1887/17/1872 dated 12.06.2017

Kindly refer to the memo quoted above the undersigned sends herewith above noted estimates amounting to **Rs. 2245879.00** only for on ward transmission to the competent authority duly countersigned by him on the body of the estimates no – **8 of 2017-18** for administrative approval and placement of fund to P.W.D. in favour of the undersigned. The minor error occurs in the calculation due to rounding of amounts. It is also to be mentioned that these estimates will valid for 2017-18.

As per discussion with The Executive Engineer, Electrical the estimate of Electrical portion will be send separately from his end.

Enclosure: - Technically sanctioned copies of
Estimates No – 8
(in Duplicate)


Executive Engineer, (P.W.D.)
Howrah Construction Division



Name of work: Preliminary cost estimate for construction of a new Plant cum Manifold room for Medical Gas Pipeline System at Uluberia Sub-Divisional Hospital , Uluberia, Howrah.

REPORT

Estimate NO. 8
2017 2018 Howrah
Construction Division (PWD)

This Rough Cost Estimate has been framed to meet up the probable expenditure for the aforesaid work as per requisition of the chief medical officer of health & secretary, DH & FWS Howrah and verbal instruction of the Executive Engineer, Howrah Construction Division ,P.W.D.

This estimate has been considered as per drawing(enclosed) & the site has been shown by hospital authority.

Accordingly, this Rough Cost Estimate has been prepared as per Volumetric rate taken vide Memo No 1757/CE/PWD dt. 10/08/2010 of the Chief Engineer, PWD.

Thus, the estimated amount stands at Rs.2245879.00 (Rupees Twenty Two Lakh Forty Five Thousands Eight Hundred Seventy Nine) Only

[Signature]
06/07/2017

Junior Engineer(PWD),section - II
Uluberia Construction Sub Division

Assistant Engineer(PWD)

Uluberia Construction Sub Division

[Signature]
06/07/17

Executive Engineer(PWD)

Howrah Construction Division

[Signature]
06/07/17

Name of work: Preliminary cost estimate for construction of a new Plant cum Manifold room for Medical Gas Pipeline System at Uluberia Sub-Divisional Hospital, Uluberia, Howrah.

		Quantity	Unit		Rate	Amount
1	Structural cost of the Plant cum Manifold Room. $82.75 \times (0.6 + 0.9 + 4.62 + 5 + 4.5) = 544.08$	544.08	cum	@Rs	3250.00	1768260.00
2	Cost for internal sanitary & plumbing works (15% of structural cost)	15%	of	@Rs	265239.00	265239.00
3	Cost for anti termite treatment (1% of structural cost)	1.00%	of	@Rs	17682.60	17682.60
4	Cost for surface drain with plinth protection $Rs.(3152 + 860) = Rs. 4012$	30	m	@Rs	4012.00	120360.00
5	Cost for land filling $12.75 \times 6.5 \times 30 = 24.86$	24.86	cum	@Rs	358.96	8923.75
6	Add 3% contingency					65413.96
					Total	2245879.31

21,80,465.00

(Rupees Twenty Two Lakh Forty Five Thousands Eight Hundred Seventy Nine) Only

Add 4% administrative charge 87,219.00
22,67,684.00

JE
06/07/17
JE, UCSD,
A.W.Dte.

Technically

SANCTIONED FOR RS. 22,45,879.00
RUPEES... Twenty Two Lakh Forty Five thousand Eight Hundred Seventy Nine only.

S. Moha
WBMSCL (SDE)
18/07/17

Checked
Grah
21/7/17

06/07/17
Executive Engineer (P.W.D.)
Howrah Construction Division

Consultant Project Eng. (Civil)
West Bengal Medical Services Corporation Ltd.

Name of work: Preliminary cost estimate for construction of a new Plant cum Manifold room for Medical Gas Pipeline System at Uluberia Sub-Divisional Hospital , Uluberia, Howrah.

REPORT

Estimate No. 8
~~2007~~ 2008 Howrah
Construction Division (PWD)

This Rough Cost Estimate has been framed to meet up the probable expenditure for the aforesaid work as per requisition of the chief medical officer of health & secretary, DH & FWS Howrah and verbal instruction of the Executive Engineer, Howrah Construction Division ,P.W.D.

This estimate has been considered as per drawing(enclosed) & the site has been shown by hospital authority.

Accordingly, this Rough Cost Estimate has been prepared as per Volumetric rate taken vide Memo No 1757/CE/PWD dt. 10/08/2010 of the Chief Engineer, PWD.

Thus, the estimated amount stands at Rs.2245879.00 (Rupees Twenty Two Lakh Forty Five Thousands Eight Hundred Seventy Nine) Only

[Handwritten signature]
06/07/17

Junior Engineer(PWD),section - II
Uluberia Construction Sub Division

Assistant Engineer(PWD)
Uluberia Construction Sub Division

[Handwritten signature]
06/07/17
Executive Engineer(PWD)
Howrah Construction Division

**Name of work: Preliminary cost estimate for construction of a new Plant cum
Manifold room for Medical Gas Pipeline System at Uluberia Sub-Divisional Hospital
, Uluberia, Howrah.**

		Quantity	Unit		Rate	Amount
1	Structural cost of the Plant cum Manifold Room. $82.75 \times (0.6 + 0.9 + 4.62 + 5 + 4.5) = 544.08$	544.08	cum	@Rs	3250.00 ✓	1768260.00 ✓
2	Cost for internal sanitary & plumbing works (15% of structural cost)	15%	of	@Rs	265239.00 ✓	265239.00 ✓
3	Cost for anti termite treatment (1% of structural cost)	1.00%	of	@Rs	17682.60 ✓	17682.60 ✓
4	Cost for surface drain with plinth protection Rs.(3152+860)= Rs. 4012	30	m	@Rs	4012.00 ✓	120360.00 ✓
5	Cost for land filling $12.75 \times 6.5 \times 30 = 24.86$	24.86	cum	@Rs	358.96 ✓	8923.75 ✓
6	Add 3% contingency					65413.96 ✓
					Total	2245879.31 ✓

21,80,465.00

(Rupees Twenty Two Lakh Fourty Five Thousands Eight
Hundred Seventy Nine) Only

Add 4% administrative charge - 87,219.00
22,67,684.00

*JE, UCSD,
P.W.Dk.*
06/07/17

Technically SANCTIONED FOR Rs. 22,45,879.31
RUPEES Twenty Two Lakh Forty Five Thousand
Eight Hundred Seventy nine only.

06/07/17
Executive Engineer (P.W.D.)
Howrah Construction Division
06/07/17