

WEST BENGAL MEDICAL SERVICES CORPORATION LTD.

(Wholly Owned by the Government of West Bengal)

CIN: U85110WB2008SGC126373

Regd. Off. : Swasthya Sathi, GN-29, Sector-V, Salt Lake, Kolkata-700091

Telephone: (033) 40340300 | Fax: (033) 40340400

E-mail: info@wbmsc.gov.in | Website: www.wbmsc.gov.in

Memo No.: WBMSC/AAES- 769/4231

Date: 24/11/2017


ORDER

Administrative Approval & Expenditure Sanction is hereby accorded for 'Electrical work relating to Construction of new plant cum manifold room for Medical Gas Pipe Line System (MGPS) at Uluberia SDH, district Howrah' at an estimated cost of Rs. 6,20,060.00 (Rupees Six Lakh Twenty Thousand and Sixty) only against fund allotment No: 1518(Sanction)/HF/P/P&B/MS/W-55/2017 Dated 23/11/2017

The details are as follows:

SI No	Schemes	Amount (Rs)
1	Electrical work relating to Construction of new plant cum manifold room for Medical Gas Pipe Line System(MGPS) at Uluberia SDH, district Howrah	6,04,937.00
2	Contingency @ 2.5%	15,123.00
Total		6,20,060.00

The work will be executed by the Executive Engineer, P.W.D Howrah Electrical Division & Ex-Officio Executive Engineer West Bengal Medical Services Corporation Limited, as per norms stated in the order of the Health & Family Welfare Dept. M.S. Branch, vide No. HF/O/MS/384/W-39-12 dt. 01.06.2012 read with Notification No. 86-W(C)-1M-106/11 dt. 06.02.2012 and Memorandum no 37-W(C)-1M-106/11 dated 17.01.2012 of Public Works Department, Government of West Bengal.


Managing Director
Date: 24/11/2017

Memo No: WBMSC/AAES-769/4231/1(10)

Copy forwarded for information and necessary action to:

1. Joint Secretary, M.S. Branch, Dept. of Health & Family Welfare
2. CMOH, Howrah
3. Superintendent, Uluberia SDH
4. Superintending Engineer, PWD, Presidency Electrical Circle & Ex-Officio Superintending Engineer, West Bengal Medical Services Corporation Limited
5. Manager (Accounts), West Bengal Medical Services Corporation Limited.
6. Executive Engineer, P.W.D Howrah Electrical Division & Ex-Officio Executive Engineer West Bengal Medical Services Corporation Limited
7. Consultant Project Engineer (Civil), West Bengal Medical Services Corporation Limited
8. Consultant Mechanical Engineer, West Bengal Medical Services Corporation Limited
9. Consultant Electrical Engineer, West Bengal Medical Services Corporation Limited
10. Office Copy.


Managing Director



GOVERNMENT OF WEST BENGAL
Public Works Department
OFFICE OF THE EXECUTIVE ENGINEER
HOWRAH ELECTRICAL DIVISION
ONKARMAL JETIA ROAD, HOWRAH - 711103
Phone No: 033-2688-0083/033-2688-0206

Memo No:1368

Date: - 13.07.2017

To

The Managing Director & Secretary
Health & FW Department.
W.B.M.S.C.L.
G.N. 29, Swasthya Bhavan
Sector -V, Salt Lake City
Kolkata - 700091

Sub- Construction of a new plant cum manifold room for medical gas pipe line system at Uluberia Sub-Divisional Hospital, Uluberia.-- Electrical Installation works.

Ref- Managing Director & Secretary, Health & FW Department memo no. WBMSC/PROC/1887/17/1872 Dt. 12.06.2017

Sir,

In reference to the captioned subject, this office Estimate No.-02/HED/UESD of 2017-18 in a tune of ₹ ~~6,20,060/-~~ ^{6,29,131.2} (Rupees ~~Six Lakh Twenty Thousand Sixty~~ only) in quadruplicate is being sent herewith for favour of your kind disposal for according administrative approval and allotment of for taking further action from this end.

Encl: - As stated.

[Signature]

Executive Engineer, PWD
Howrah Electrical Division
Govt. of West Bengal.

Memo No:1368/1(3)

Date: 13.07.2017

Copy forwarded for information and necessary action to:-

- 1) The C.M.O.H, Howrah.
- 2) The Superintendent, Uluberia Sub-Divisional Hospital.
- 3) The Assistant Engineer, PWD, Uluberia Electrical Sub-Division.

[Signature]

Sd/- P. Khan
Executive Engineer, PWD
Howrah Electrical Division
Govt. of West Bengal.

ROUGH COST ESTIMATE

NAME OF WORK :

Construction of a new plant cum manifold room for medical gas pipe line system at Uluberia Sub-Divisional Hospital, Uluberia. - Electrical Installation works.

REFERENCE :

Managing Director & Secretary, Health & FW Department memo no. WBMSC/PROC/1887/17/1872 dt 12/06/2017.

REPORT :

This estimate has been framed to meet up the probable expenditure of above mentioned job. According to the enclose drawing and present site condition this estimate has been framed. Here have considered cable laying form nearest capable source, electrical distribution system, illumination, ventilation and DG connection provision. All the rates are including of all taxes. Hence, this framed estimate forwarded to you for your administrative approval and allotment of fund please.

Sl. No.	Description of Work	Quantity	Rate	Unit	Amount
1	Supply and laying of 4C x 35sqmm Al, Ar, XLPE insulated cable in under ground trench with GI pipe protection, inspection pits etc. Glanding & termination charges included. <i>22.0 mtrs.</i>	1 Item	Rs. 324,258.00	Item	Rs. 324,258.00
2	Supply and fixing of 4W VTPN DB with 80A MCCB incommer with outgoing 6-32A SP MCB and 63A TP MCB, cable end boxes. Also Supply and fixing of 2+6W SPNMCBDB with 40A DP isolator incommer with 6-32A SPMCB outgoing. Also Supply & fixing of 4pole 125A onload change over switches with cable ens boxes. <i>2 sets.</i>	1 Item	Rs. 89,210.00	Item	Rs. 89,210.00
3	Supply & installation of concealed point wiring with 3 x 1.5sqmm Cu fl. Wire along with inspection boxes, cirular box, bakelite covers, piano type switches etc. Along with concealed distribution wiring with following sizes cu wires, <i>18 2A, 10 mtr AV)</i> 3 x 1.5sqmm, <i>40 mtr</i> 2 x 2.5 + 1 x 1.5sqmm, <i>60 mtr.</i> <i>(Timer & MS)</i> 2 x 4.5 + 1 x 2.5sqmm. <i>62 mtr.</i>	1 Item	Rs. 88,666.00	Item	Rs. 88,666.00
4	Supply and installation of 20W LED box type tube light fittings single and double with 6W LED bulk head fittings, 1200mm sweep ceiling fans, <i>8 1/2"</i> CI fan box, 12inch heavy duty exhaust fans. <i>estimate in</i> <i>Unit 2</i> <i>head 2</i>	1 Item	Rs. 69,860.00	Item	Rs. 69,860.00
5	Supply and fixing of 5A on boards sockets, 20A separate switch and socket, 4x 5A plug boards, 20A SPN Insustrial plug socket and 32A TPN industrial plug sockets.	1 Item	Rs. 13,359.00	Item	Rs. 13,359.00
6	Supply and installation of earthing arrangements with earth bus bar and strips 25 x 3mm.	1 Item	Rs. 19,584.00	Item	Rs. 19,584.00
Sub-Total					Rs. 604,937.00
Contingency @ 2.5%					Rs. 15,123.43
Total					Rs. 620,060.00

Rupees Six Lakh Twenty Thousand Sixty Only

A. Nij
Junior Engineer (PWD)
Uluberia Electrical Section I

DG
Assistant Engineer (PWD)
Uluberia Electrical Sub Division

Pooja K...
Executive Engineer (PWD)
Howrah Electrical Division

*Adding Administrative charges of WBMSCL 29,197.00 @ 4%
Rs. 29,139.20*

Checked:
Siddhanta
18/11/17
Consultant Eng. (Elect.)
Bengal Medical Services Corporation Ltd.

ROUGH COST ESTIMATE

NAME OF WORK :

Construction of a new plant cum manifold room for medical gas pipe line system at Uluberia Sub-Divisional Hospital, Uluberia. -
Electrical Installation works.

REFERENCE :


Managing Director & Secretary, Health & FW Department memo no. WBMSC/PROC/1887/17/1872 dt 12/06/2017.


REPORT :


This estimate has been framed to meet up the probable expenditure of above mentioned job. According to the enclosed drawing and present site condition this estimate has been framed. Here have considered cable laying from nearest capable source, electrical distribution system, illumination, ventilation and DG connection provision. All the rates are including of all taxes. Hence, this framed estimate forwarded to you for your administrative approval and allotment of fund please.

Sl. No.	Description of Work	Quantity	Rate	Unit	Amount
1	Supply and laying of 4C x 35sqmm Al, Ar, XLPE insulated cable in under ground trench with GI pipe protection, inspection pits etc. Glanding & termination charges included.	1 Item	Rs. 324,258.00	Item	Rs. 324,258.00
2	Supply and fixing of 4W VTPN DB with 80A MCCB incommer with outgoing 6-32A SP MCB and 63A TP MCB, cable end boxes. Also Supply and fixing of 2+6W SPNMCBDB with 40A DP isolator incommer with 6-32A SPMCB outgoing. Also Supply & fixing of 4pole 125A on load change over switches with cable end boxes.	1 Item	Rs. 89,210.00	Item	Rs. 89,210.00
3	Supply & installation of concealed point wiring with 3 x 1.5sqmm Cu fl. Wire along with inspection boxes, circular box, bakelite covers, piano type switches etc. Along with concealed distribution wiring with following sizes cu wires, 3 x 1.5sqmm, 2 x 2.5 + 1 x 1.5sqmm, 2 x 4.5 + 1 x 2.5sqmm.	1 Item	Rs. 88,666.00	Item	Rs. 88,666.00
4	Supply and installation of 20W LED box type tube light fittings single and double with 6W LED bulk head fittings, 1200mm sweep ceiling fans, CI fan box, 12inch heavy duty exhaust fans.	1 Item	Rs. 69,860.00	Item	Rs. 69,860.00
5	Supply and fixing of 5A on boards sockets, 20A separate switch and socket, 4x 5A plug boards, 20A SPN industrial plug socket and 32A TPN industrial plug sockets.	1 Item	Rs. 13,359.00	Item	Rs. 13,359.00
6	Supply and installation of earthing arrangements with earth bus bar and strips 25 x 3mm.	1 Item	Rs. 19,584.00	Item	Rs. 19,584.00
Sub-Total Rs.					604,937.00
Contingency @ 2.5%					Rs. 15,123.43
Total Rs.					620,060.00

Rupees Six Lakh Twenty Thousand Sixty Only


Junior Engineer (PWD)
Uluberia Electrical Section I


Assistant Engineer (PWD)
Uluberia Electrical Sub Division


Executive Engineer (PWD)
Howrah Electrical Division

ROUGH COST ESTIMATE

NAME OF WORK :

Construction of a new plant cum manifold room for medical gas pipe line system at Uluberia Sub-Divisional Hospital, Uluberia. -
Electrical Installation works.

REFERENCE :

Managing Director & Secretary, Health & FW Department memo no. WBMSC/PROC/1887/17/1872 dt 12/06/2017.


REPORT :

This estimate has been framed to meet up the probable expenditure of above mentioned job. According to the enclosed drawing and present site condition this estimate has been framed. Here have considered cable laying from nearest capable source, electrical distribution system, illumination, ventilation and DG connection provision. All the rates are including of all taxes. Hence, this framed estimate forwarded to you for your administrative approval and allotment of fund please.

Sl. No.	Description of Work	Quantity	Rate	Unit	Amount
1	Supply and laying of 4C x 35sqmm Al, Ar, XLPE insulated cable in under ground trench with GI pipe protection, inspection pits etc. Glanding & termination charges included.	1 Item	Rs. 324,258.00	Item	Rs. 324,258.00
2	Supply and fixing of 4W VTPN DB with 80A MCCB incommer with outgoing 6-32A SP MCB and 63A TP MCB, cable end boxes. Also Supply and fixing of 2+6W SPNMCBDB with 40A DP isolator incommer with 6-32A SPMCB outgoing. Also Supply & fixing of 4pole 125A on load change over switches with cable end boxes.	1 Item	Rs. 89,210.00	Item	Rs. 89,210.00
3	Supply & installation of concealed point wiring with 3 x 1.5sqmm Cu fl. Wire along with inspection boxes, circular box, bakelite covers, piano type switches etc. Along with concealed distribution wiring with following sizes cu wires, 3 x 1.5sqmm, 2 x 2.5 + 1 x 1.5sqmm, 2 x 4.5 + 1 x 2.5sqmm.	1 Item	Rs. 88,666.00	Item	Rs. 88,666.00
4	Supply and installation of 20W LED box type tube light fittings single and double with 6W LED bulk head fittings, 1200mm sweep ceiling fans, CI fan box, 12inch heavy duty exhaust fans.	1 Item	Rs. 69,860.00	Item	Rs. 69,860.00
5	Supply and fixing of 5A on boards sockets, 20A separate switch and socket, 4x 5A plug boards, 20A SPN industrial plug socket and 32A TPN industrial plug sockets.	1 Item	Rs. 13,359.00	Item	Rs. 13,359.00
6	Supply and installation of earthing arrangements with earth bus bar and strips 25 x 3mm.	1 Item	Rs. 19,584.00	Item	Rs. 19,584.00
Sub-Total					Rs. 604,937.00
Contingency @ 2.5%					Rs. 15,123.43
Total					Rs. 620,060.00

Rupees Six Lakh Twenty Thousand Sixty Only


Junior Engineer (PWD)
Uluberia Electrical Section I


Assistant Engineer (PWD)
Uluberia Electrical Sub Division


Executive Engineer (PWD)
Howrah Electrical Division