



WEST BENGAL MEDICAL SERVICES CORPORATION LTD.
(Wholly owned by the Government of West Bengal)
Swasthya Sathi, GN-29, Sector-V, Salt Lake, Kolkata-700 091.

CORRIGENDUM - I

FOR

**SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF 20(TWENTY) NOS.
WALK-IN-COOLER (WIC) AT DIFFERENT DISTRICT OF WEST BENGAL**

Bid Reference No.: WBMSCL/NIT- 67/ 2020

Dated - 08/06/2020

Sl. No.	Section	Clause/ Sl. No.	Current Clause / Provision	Changed Clause / Provision
1	ANNEXURE-A Specification of Walk In Cooler BASIS OF DESIGN - WALK IN COOLER	14. Flooring	60mm Puf Panel with marine ply and chequered sheet	<i>60 mm PUF Panel with 6 mm marine ply(century/ green ply) and 2 mm Al chequered sheet</i>
2	ANNEXURE-A Specification of Walk In Cooler BASIS OF DESIGN - WALK IN COOLER	16. IDU- Refrigeration unit	IDU HOUSING - SS-304/powder coated GI	<i>IDU HOUSING</i> - SS-304
3	ANNEXURE- A Specification of Walk In Cooler BASIS OF DESIGN - WALK IN COOLER	17. CDU- Refrigeration unit	COMPRESSOR MODEL - CR22 or equivalent	<i>COMPRESSOR MODEL</i> - R 404a / R410/ R410a fitted <i>compressor</i>

Sl. No.	Section	Clause/ Sl. No.	Current Clause / Provision	Changed Clause / Provision
4	ANNEXURE-A Specification of Walk In Cooler BASIS OF DESIGN - WALK IN COOLER	20. Voltage stabilizer	7.5 KVA Voltage Stabilizer [Range 145V – 280V] X 2 Sets [230V/1PH/ 50Hz] make- AVO/Quatron control/microtek	<i>5.0 KVA Voltage Stabilizer [Range 145V – 280V]</i> X 2 Sets [230V/1PH/ 50Hz] make- AVO/Quatron control/microtek
5	ANNEXURE-A Specification of Walk In Cooler BASIS OF DESIGN - WALK IN COOLER	23. Make of WIC	CARRIER/BLUE STAR	CARRIER/BLUE STAR/ <i>ICE MAKE</i>
6	ANNEXUR E-A Schedule of items WALK IN COOLER	4.	60 mm thick PUF Panel insulation with anti Skid GI Sheet Flooring – 1 set	<i>60 mm PUF Panel with 6 mm marine ply(century/ green ply) and 2 mm Al chequered sheet – 1 set</i>

Sl. No.	Section	Clause/ Sl. No.	Current Clause / Provision	Changed Clause / Provision
7	ANNEXUR E-A Schedule of items WALK IN COOLER	9	7.5 KVA voltage stabilizer- 2 sets	5.0 KVA voltage stabilizer- 2 sets
8	ANNEXUR E-A Schedule of items WALK IN COOLER	22	Provision of racks- 1 item	<i>Deleted</i>

Sd/-
General Manager
WBMSCL