

# WEST BENGAL MEDICAL SERVICES CORPORATION LTD

(Wholly Owned by the Government of West Bengal)

CIN:U85110WB2008GC126373 2008-09

Regd. Off. Swasthya Sathi, GN-29, Sector-V, Salt Lake

Phone: 033 40340300 Fax: 033 40340400 email id: [info@wbmsc.gov.in](mailto:info@wbmsc.gov.in)

## Name of work:

Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH

## NOTICE INVITING TENDER

**Memo No: WBMSCL/NIT- 210 /2021**

**Dated – 29 /06/2021**

Managing Director, West Bengal Medical Services Corporation Limited, Swasthya Sathi, GN-29, Sector-V, Kolkata - 700 091, invites sealed bids from eligible contractors with experience of similar nature of work for the work **Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.**

The details may be available at Notice Board of WBMSCL & website [www.wbmsc.gov.in](http://www.wbmsc.gov.in) and to be submitted (offline) on or before 1:00 P.M. on 07/07/2021 at Site Office of WBMSCL at Balurghat SSH.

No of Site	1 no.
Estimated Amount	109634.00
Bid Security/EMD	The bidder will have to deposit earnest money Rs. 2193.00 (In the form of DD from a scheduled bank drawn in favour of "West Bengal Medical Services Corporation Ltd").
Security Deposit	3% of the contract amount to be deducted from the Bill for each work.
Releasing of Security Deposit	One year from the date of completion of work
Tender Publication Date	01/07/2021
Last date of Submission of Tender	07/07/2021 Upto 1:00 PM
Date of Opening of Tender Document	07/07/2021 at 1:30 PM
Validity of Quotation	120 days from the date of opening of the financial bid of the tender.
Time allowed for completion of Work	7 days from the date of Work order for both the work

Eligibility of participating bidder	<p>Bonafied reliable and resourceful firm having executed similar nature of Work.</p> <p>Intending tenderers should produce credentials of a similar nature of completed work of the minimum value of 40% of the estimated amount put to tender.</p>
Bid opening Venue	Balurghat SSH

Prospective bidders are requested to submit the bid in a sealed cover addressed to the Managing Director, West Bengal Medical Services Corporation Ltd, Swasthya Sathi, GN -29, Sector – V, Salt Lake, Kolkata – 700091 within the stipulated date & time.

Bidders are instructed to submit their bid consisting of two sealed envelope called “Qualifying Bid” & “Financial Bid” in the tender box of WBMSCL by hand. Bid will not be taken by postal system/courier.

**Documents comprising the bid:** (Bidders are instructed to submit their bid consisting of two sealed envelope called Qualifying Bid & Financial Bid.)

**The Qualifying Bid shall comprise the following: -**

- a. PAN No.
- b. GST registration no.
- c. IT Return for the assessment year of 2020-21.
- d. Experience in similar field
- E. Duly signed NIT
- F. Trade License

**The Financial Bid shall comprise the following:**

Applicable Rate Schedules as per printed format on the letter head of the intending bidder.

(Rate must be given in the B.O.Q. provided below, on the letter head of the intending bidder. Rate is inclusive of all taxes, charges in respect of all the sites/location. Any taxes, charges etc shown separately will not be considered. Rate Quote in any other format will be treated as cancelled).

The intending bidder(s) required to quote the rate (percentage above/below/at par) over the total estimated cost put to tender considering that no escalation and / or price adjustment will be allowed by the department under any circumstances.

**A bidder shall have to furnish signed "Financial Bid" on their letter head.** The financial bid of only of those bidders will be opened who meet all the requirements of the technical bid.

Failing to fulfill the requirements and eligibility criteria set in the bid document will make the bidders Bid invalid. WBMSCL reserves the right to cancel or reject any or all of the Bids without assigning any reason whatsoever.

Sd/-  
**Managing Director &  
Commissioner, H & F W Department**

## BILL OF QUANTITY

Name of Work : Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.

Item No.	P A R T I C U L A R S	Quantity	Unit	Rate [ In Rs. ]	Amount [ In Rs. ]
	Aluminium Works				-
<b>1</b>	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Annodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer-In-Charge. (Payment will be made on finished length of the work).				-
	(A) In 10-12 Micron thickness Annodizing film				-
	I) Natural white				-
	<b>k) Movable door shutter</b>				
	<b>i) Door Frame (Top &amp; Sides)</b>				
		19.800	Mtr.	356.33	7,055.29
	<b>ii) Shutter</b>				
	<b>a) Top Rail</b>				
		7.200	Mtr.	343.88	2,475.97
	<b>b) Bottom Rail</b>				
		7.200	Mtr.	598.40	4,308.51
	<b>c) Lock Rail</b>				
	1st Floor	2.400	Mtr.		
		7.200	Mtr.	426.46	3,070.53
	<b>d) Door Vertical</b>				
		25.200	Mtr.	375.56	9,464.07
	<b>Glazing clip</b>				
		129.600	Mtr.	56.56	7,330.18
<b>2</b>	(i) Door stopper.(Brass)	6.000	Each	132.35	794.10
<b>3</b>	Labour charge for fabrication and installation of composite door, window, partitions made from annodized extruded alloy aluminium sections for the following units:-				-

Name of Work : Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.

Item No.	P A R T I C U L A R S	Quantity	Unit	Rate [ In Rs. ]	Amount [ In Rs. ]
	(B) Partly glazed partly panelled or fully glazed single leaf alunminium swing door made of extruded and annodized alloy aluminium sections, fabrication including cutting to proper shape and size, drilling and aligning, fitted with heavy duty hydraulic action floor sping placed in the floor with mending damages,with top pin assembly of approve make and brand, fitted with in built locking arrangement, flush bolt, glazing clips and all other necessary fittings, fixtures, adhesives and joineries, cutting glass of approved make to requisite shape and size fitting with dry set neoprene or EPDM gasketing, cutting to requisite shape and size panel board (prelaminated particle block) fixing them with glazing clips as per drawing, specification and direction of Engineer in charge.				-
	1st Floor	5.760	SqM	1,390.19	8,007.48
	2nd Floor	5.760	SqM	1,403.76	8,085.67
	5th Floor	5.760	SqM	1,449.01	8,346.30
4	Supplying EPDM gasket of approved make and brand as per direction of Engineer in charge.				-
	<b>a) EPDM / weather gasket for outer frame and mullion.</b>				
	iii) weather gasket/wool pile for door vertical.				-
		25.200	Mtr.	21.49	541.62
5	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987; (A) clear, toughened glass conforming to IS: 2553-1992 (part-II)				-
	<b>v) 6mm thick clear glass.</b>				-
		7.560	SqM	687.77	5,199.54
6	Supplying 4 lever mortice lock or any approved make and brand as per direction of the Engineer-in -Charge.				-

**Name of Work : Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.**

Item No.	P A R T I C U L A R S	Quantity	Unit	Rate	Amount
				[ In Rs. ]	[ In Rs. ]
	i) 150 mm.				
		3.000	Each	427.59	1,282.78
7	(A) Supplying Aluminium casted body hydraulic door closer as per I.S.I.				-
		6.000	Each	718.31	4,309.87
	(C) Supplying Heavy Duty Aluminium Handle (EBCO Type) (Natural White)				-
		12.000	Each	108.60	1,303.14
	(D) Supplying Aluminium casted body Butt Hinge (KOBRA type). (Natural white)				-
		24.000	Each Set	63.35	1,520.33
8	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws:				-
	(iii) 100mm long x 10mm dia. bolt.				
		6.000	Each	59.95	359.72
9	Filling the gap in between aluminium frame & adjacent RCC / Brick/ Stone work by providing weather silicon sealant over 6mm dia backer rod of approved quality as per architectural drawings and direction of Engineer-in-Charge complete. Upto 5 mm depth and 5 mm width				-
	1st Floor	4.200	Mtr.	81.45	342.07
	2nd Floor	4.200	Mtr.	84.84	356.33
	5th Floor	4.200	Mtr.	95.02	399.09
10	i) Fixed partitions. (Unsupported length of vertical member upto 1.5 mtr. Height of both ends of vertical member restrained but panels within 0.9 sq.m.)				

**Name of Work : Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.**

Item No.	P A R T I C U L A R S	Quantity	Unit	Rate	Amount
				[ In Rs. ]	[ In Rs. ]
	i) Top , bottom & side member.				
		16.200	Mtr.	363.12	5,882.47
	ii) Intermediate member.				
		1.800	Mtr.	383.48	690.26
	iii) Glazing clip.				
		36.000	Mtr.	56.56	2,036.16
<b>11</b>	Labour charge for fabrication and installation of composite door, window, partitions made from annodized extruded alloy aluminium sections for the following units:-				
	D) Partly glazed and partly panelled partition or fixed glazing made of extruded and anodised alloy aluminium sections, fabrications after cutting to proper shape and size, drilling and aligning fitted with inbuilt locking arrangement cutting the glass / board (prelaminated / particle / block) to requisite shape and size moulding the edges fitted and fixed glazing clips and dry set neoprine /EPDM gasket, along with all other necessary arrangements for fixing the partition to walls, floors, beams, columns polysulphide sealant for water proofing if necessary complete in all respect as per drawing and specifications and direction of the Engineer in charge.				
	I) For partitions using section of size:				
	a) 63.50 mm x 38.10 mm				
	1st Floor	0.720	SqM	837.09	602.70
	2nd Floor	0.720	SqM	850.66	612.48
	5thFloor	0.720	SqM	895.91	645.06

Name of Work : Fixing of partition wall with gate between proposed COVID ward and Children Ward & SNCU in Balurghat SSH.

Item No.	P A R T I C U L A R S	Quantity	Unit	Rate	Amount
				[ In Rs. ]	[ In Rs. ]
<b>12</b>	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming groves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP)				-
	(b) 4mm thick (0.50mm Al.+3.0mm LDPE +0.50mm Al. PVDF coating)	-			-
	1st Floor	2.520	Sq.M	3,255.59	8,204.10
	2nd Floor	2.520	Sq.M	3,255.59	8,204.10
	5th Floor	2.520	Sq.M	3,255.59	8,204.10
<b>Total</b>					<b>109,634.02</b>
<b>SaY, Rs.</b>					<b>109,634.00</b>
Quoted Percentage of rate (Above + )					
Quoted Percentage of rate (At Par )					
Quoted Percentage of rate (Below - )					
Quoted Percentage of rate in words					

**Sd/-**  
**Managing Director & Commissioner,**  
**H & F W Department**